Haryana Government Gazette

Published by Authority

© Government of Haryana

No. 46–2025] CHANDIGARH, MONDAY, NOVEMBER 17, 2025 (KARTIKA 26, 1947 SAKA)

PART-I

Notifications, Orders and Declarations by Haryana Government

HARYANA GOVERNMENT

PUBLIC WORKS DEPARTMENT (BUILDING AND ROADS BRANCH)

Notification

The 29th October, 2025

No. E-in-C/PWD (B&R) / Chandigarh DC/03.—

THESE AMENDMENTS WILL BE APPLICABLE FROM THE DATE OF GAZETTE NOTIFICATION.

Addenda and Corrigenda to the Haryana PWD Schedule of Rates 2021 (Third Edition)

A&C Slip No.13

Dated: 29/10/2025.

In the the Haryana PWD Schedule of Rates 2021 (Third Edition) the following items have been included:

Sr. No.	HSR Item No.	Description of item.	Unit	Through rates
1.	32.71	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid door / window / Clerestory windows & other Frames/ Chowkhat comprising of virgin PVC polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/ wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750 kg/cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm2, modulus of elasticity 900 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in position with M.S hold fast/lugs/SS dash fasteners of required dia and length complete as per direction of Engineer-ln- Charge. (M.S hold fast/lugs or SS dash fasteners shall be paid for separately). Note: For WPC solid door/window frames, minus 5 mm tolerance in dimensions i.e depth and width of profile shall be acceptable. Variation in profile dimensions on plus side shall be acceptable but no extra payment on this account shall be made.		

	32.71.1	Frame size 45 x 70 mm	Mtr.	478.54
	32.71.2	Frame size 45 x 85 mm	Mtr.	628.03
	32.71.3	Frame size 50 x 100 mm	Mtr.	642.51
	32.71.4	Frame size 50 x 125 mm	Mtr.	729.29
	32.71.5	Frame size 65 x 100 mm	Mtr.	753.42
	32.71.6	Frame size 65 x 125 mm	Mtr.	936.68
	32.71.7	Frame size 65 x 150 mm	Mtr.	1110.41
2.	32.72	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-ln- Charge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately)		
	32.72.1	30 mm thick	Mtr.	2946.92
	32.72.2	35 mm thick	Mtr.	3400.24
3.	32.73	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid decorative type flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant. WPC to be laminated with PVC foil of minimum 14 microns thick of approved design pasted with hot melt adhesive on both faces of shutter and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-in-Charge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately).		
	32.73.1	30 mm thick	Mtr.	3229.97
	32.73.2	35 mm thick	Mtr.	3683.29

A&C Slip No.14
Dated: 29/10/2025.

In the the Haryana PWD Schedule of Rates 2021 (Third Edition) the following amendement have been done:

Existing Item:

Sr. No.	HSR Item No.	Description of item.	Unit	Labour rates	Machinery rates	Material rates	Through rates.
1.	21.99.12	Providing, lowering, laying, aligning, fixing in position and jointing at all level/ depths ISI marked HDPE pipes of PE-80 grade and PN-4 for sewer application as per IS 14333-2022 (amended up to date) in trenches in complete including cost of HDPE 'Specials,	Cum	69	0	500	569

		labour, sectional hydro testing (including the cost and conveyance of water to site for testing) and commissioning as per Technical Specifications and as per direction of Engineer. Note: E/w to be measured and paid separately. Rate includes cost of all specials like bends, tees required during laying of pipe line along required alignment. 140mm outside dia					
2.	21.99.13	Providing, lowering, laying, aligning, fixing in position and jointing at all level/ depths ISI marked HDPE pipes of PE-100 grade and PN-6 for sewer application as per IS 14333-2022 (amended up to date) in trenches in complete including cost of HDPE 'Specials, labour, sectional hydro testing (including the cost and conveyance of water to site for testing) and commissioning as per Technical Specifications and as per direction of Engineer. Note: E/w to be measured and paid separately. Rate includes cost of all specials like bends, tees required during laying of pipe line along required alignment. 140mm outside dia.	Cum	69	0	607	676

Amended Item:

Sr. No.	HSR Item No.	Description of item.	Unit	Labour rates	Machinery rates	Material rates	Through rates.
1.	21.99.12	Providing, lowering, laying, aligning, fixing in position and jointing at all level/ depths ISI marked HDPE pipes of PE-80 grade and PN-4 for sewer application as per IS 14333-2022 (amended up to date) in trenches in complete including cost of HDPE 'Specials, labour, sectional hydro testing (including the cost and conveyance of water to site for testing) and commissioning as per Technical Specifications and as per direction of Engineer. Note: E/w to be measured and paid separately. Rate includes cost of all specials like bends, tees required during laying of pipe line along required alignment. 140mm outside dia	Rmt.	69	0	500	569

2.	21.99.13	Providing, lowering, laying, aligning, fixing in position and jointing at all level/ depths ISI marked HDPE pipes of PE-100 grade and PN-6 for sewer application as per IS 14333-2022 (amended up to date) in trenches in complete including cost of HDPE 'Specials, labour, sectional hydro testing (including the cost and conveyance of water to site for testing) and commissioning as per Technical Specifications and as per direction of Engineer. Note: E/w to be measured and paid separately. Rate includes cost of all specials like bends, tees required during laying of pipe line along required alignment. 140mm outside dia.	Rmt.	69	0	607	676

A&C Slip No.15

Dated: 29/10/2025.

In the the Haryana PWD Schedule of Rates 2021 (Third Edition) the following items have been included:

Sr. No.	HSR Item No.	Description of item.	Unit	Labour rates	Machinery rates	Material rates	Through rates.
1	10.110	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 1200x2400 mm	Sqm.	151.24	-	2302.99	2454.23
2	10.111	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours and shade, in skirting, dados, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement and matching pigments etc. complete. Size of Tile 1200x2400 mm	Sqm.	181.20	-	2292.00	2473.20

3	7.105	Brick masonry with Lakhori / Nanakshahi bricks 150 X 75 X 20 mm laid in cement mortar (1 cement: 4 sand) or in lime mortar in proportion similar to the existing traditional lime mortar mixed with organic / chemical additives as per directions of the Engineer-in-charge complete in all respect including cost of all materials, labour, necessary tools and scaffolding etc. complete in all respect. The work includes all works in any design or patterns as per the drawings in these bricks only.	Sqm.	545	-	3628	4173

HARPAL SINGH,
Convener, Central Zonal Committee,
Haryana PWD Schedule of Rates-cum-
Superintending Engineer, Ambala Circle,
PWD (B&R), Ambala Cantt.

12190—C.S.—H.G.P., Pkl.